Alabama Port Authority

Addendum to R&P or Specification Booklet

Project Name Stacker Reclaimer 2 & 3 Procurement – Electrical Switchgear Supply

Project No. 11367 **Task No.** 05 **Addendum No.** 2

To: Prospective Bidders **Date:** 5/19/2026

These items are hereby included in the bid documents by this addendum.

Item	Description
1.	Correction to Addendum 1, Item 3: SEL-535 Power Quality and Monitoring should have been SEL-351 Feeder Protection Relay.
2.	The following questions were submitted before the deadline. The responses are provided for your information. Q: If no exceptions are taken to the standard electrical requirements, is not being ISO certified a disqualifier? A: YES, Section 4.2 states that the manufacture shall be ISO Certified. ISO Certification provides protection guarantees in manufacturing of equipment. Q: The customer spec calls out "Switchboard style draw out relays." Is this a hard requirement, or can we offer standard SEL protective devices in our lineups? SEL protective devices will be acceptable. A: Draw out relays are preferred but not a hard requirement. Q: Spec calls for 65kaic rating, but can we offer 50kaic? A: NO. With existing switchgear in the building having a 65kaic rating I would not reduce the rating to 50kaic. Q: From my understanding for start-up, they just want someone on-site to oversee. Is the correct assumption? They also ask for training regarding the equipment, how in-depth of training are they requiring? A: Correct, the switchgear manufacturer is to provide onsite support during commissioning. The training should cover basic operations and maintenance information.

Please indicate your receipt of this addendum by adding the addendum number in the appropriate place in your Requisition & Proposal or Specification Book.