



Alabama Port Authority



Project Name McDuffie Terminal Dock 2 Refurbishment – Pile and Dock Repair

Location Mobile, Alabama

Project # 11703

Task # 3

June 9, 2026

Addendum 4
1 | Page

ADDENDUM NO. 4

Item	Description
NOTES	
1	Contractor Questions

11703 - Task 3 – McDuffie Terminal Dock 2 Refurbishment

Pile and Dock Repair

Addendum 4

Contractor Questions

1. Is there a Dock load value for equipment which we will need on the dock, wt per sf?
 - The live load capacity of the dock is approximately 600 psf.
2. Is the intent of the Wall repair instructions that all repaired sections end up the same opening size or is the cut out relative to the repair size?
 - The intent of the cut out is relative to the repair size as indicated by the estimated lengths provided on the drawings.
3. Will the contractor be paid for anything that goes past the quantities given in the plans? If your plans state 4 sqft for a pile and its actually 10, will the contractor be paid for the additional sqft? I ask this because I believe your quantities may be lower than actual and your line item is per pile.
 - Each pile was not measured and the surface areas shown on the drawings are an estimate based upon sample field measurements and visual approximations. It is estimated that approximately 600 cubic feet of repair mortar will be required for the piling repair but it is the contractor's responsibility to determine the actual quantities required and account for it in their bid as the price paid will be per pile as stated in the schedule of prices.
4. Can we have a compressor on the west side of Dock 2 for the duration of the project?
 - Yes, keeping a compressor on the west side of Dock 2 for the duration of the project is acceptable as long as it does not interfere with crane or Terminal operations.