Alabama Port Authority

Addendum to R&P or Specification Booklet

Project Name **McDuffie 43E Low Voltage Switchboard**

Project No. 11847 **Task No.** 2 **Addendum No.** 1

To: Prospective Bidders **Date:** 11/9/2026

The bid documents for project 11847-02 are amended to include the following clarifications

1.	This project is for procurement and delivery only. The Owner will unload the equipment from the delivery vehicle at the McDuffie Coal Terminal Warehouse.
2.	There are no seismic requirements for the Switchboard Vendor. Any Seismic will be handled by the Civil/Structure Engineering Team.
3.	The datasheet and one-line diagram show 800A-frame feeders set at 500A, while Section 5.7 calls for 800A continuous. To clarify, the breakers should be 800AF with 800A Digital Trip units set at 500A.
4.	Remote operation and separate ground-fault indication lights on all eight feeders will be considered as a best-value option, but they are not mandatory.
5.	Proof of insurance is not required for this project. A performance bond will not be required for this project.

Please indicate your receipt of this addendum by adding the addendum number in the appropriate place in your Requisition & Proposal.

Project Manager:

Pete Olivero Date: 11 / 9 / 2026

Pete Olivero, P.E.
Senior Facilities Engineer